

COPYRIGHT NOTICE

This geotechnical log and its associated data (the Document) is licensed by the Queensland Department of Transport and Main Roads under the [Creative Commons Attribution 4.0 Licence](#) (CC BY 4.0). When reusing the Document, in whole or in part, please attribute the Department as follows: "*(c) State of Queensland (Department of Transport and Main Roads) 2020, licensed under the CC BY 4.0 Licence*". This licence does not apply to the Queensland Government logo or trademarks.

LIMITATION OF LIABILITY

The CC BY 4.0 Licence contains a comprehensive Disclaimer of Warranties and Limitation of Liability. In addition, please note that this Document was prepared for Departmental use only. Reuse of the Document by anyone for any other purpose could result in error and/or loss. You should obtain professional advice before making decisions based on the contents of the Document.

When reproducing any part of this Document, you must also reproduce this limitation of liability notice in addition to the italicised attribution statement above.

Retrieved from the Queensland Geotechnical Database <http://qgd.org.au/>



**Queensland
Government**

Department of
Main Roads

ENGINEERING BOREHOLE

FOR GEOTECHNICAL TERMS AND
SYMBOLS REFER FORM F:GEOT 017/2-2004

BOREHOLE No BH11

SHEET 1 of 6

REFERENCE No H9560

PROJECT GATEWAY UPGRADE PROJECT - GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION PIER 6 - SOUTHERN FACE OF THE PILE CAP COORDINATES 10316.4 E; 167691.5 N

PROJECT No FG5388 SURFACE R.L. -1.84 DATE STARTED 10/3/05 DATUM SETP

JOB No _____ DATUM AHD DATE COMPLETED 11/3/05 DRILLER CAIRNS DRILLING

DEPTH (m)	R.L. (m)	CASING WASH BORING CORE DRILLING	ROD (%) CORE REC %	SAMPLE	MATERIAL DESCRIPTION	LITHOLOGY	INTACT STRENGTH						DEFECT SPACING (mm)	GRAPHIC LOG	ADDITIONAL DATA AND TEST RESULTS	SAMPLES TESTS	
							USC	WEATHERING	EH	VH	HM	JVL					EL
0	-1.84				ESTUARINE SANDY SILTY CLAY Dark grey to black, moist, wet, very soft to soft. Becoming more organic silty clay with depth; some partly decomposed shell fragments.												
1																	
2																	RW,-- N<1 SPT
3																	
4																	RW,-- N<1 SPT
5	-6.04				LOW GRADE COAL FINE GRAINED MAINLY DULL TO VITREOUS THINLY LAMINATED FRAGILE CARBONACEOUS SEDIMENTARY ROCK XW : Generally exhibits engineering properties of black, moist, very stiff silt.												
5	-6.84																Used roller bit below 4.2m. 0,2,18 N=20 SPT

REMARKS This borelog should be read in conjunction with the appropriate Defect Description Sheets. Defect angles have been measured with respect to a horizontal plane.

LOGGED BY
A. DISSANAYAKE (DISS)



**Queensland
Government**

Department of
Main Roads

ENGINEERING BOREHOLE

FOR GEOTECHNICAL TERMS AND
SYMBOLS REFER FORM F.GEOT 017/2-2004

BOREHOLE No BH11

SHEET 4 of 6

REFERENCE No H9560

PROJECT GATEWAY UPGRADE PROJECT - GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION PIER 6 - SOUTHERN FACE OF THE PILE CAP COORDINATES 10316.4 E; 167691.5 N

PROJECT No FG5388 SURFACE R.L. -1.84 DATE STARTED 10/3/05 DATUM SETP

JOB No _____ DATUM AHD DATE COMPLETED 11/3/05 DRILLER CAIRNS DRILLING

DEPTH (m)	R.L. (m)	CASING WASH BORING CORE DRILLING	ROD () % CORE REC %	SAMPLE	MATERIAL DESCRIPTION	LITHOLOGY	USC WEATHERING	INTACT STRENGTH	DEFECT SPACING (mm)	GRAPHIC LOG	ADDITIONAL DATA AND TEST RESULTS	SAMPLES TESTS
15	-16.84				INTERBEDDED LOW GRADE COAL / SILTSTONE & SANDSTONE. LOW GRADE COAL DOMINANT MW -SW: Pale grey to black, fine grained, laminated/interbedded, mainly medium strength with some low and high strength bnads.. Defects : Mainly lamination partings <5° (2-8/m) Becoming sandstone, dominantes between 15.5m and 16.25m; highly altered and weathered along bedding/lamination partings.	USC MH MW				Coreless	Is(50)=0.38 MPa Is(50)=1.28 MPa	x o
16				Is(50)=0.75 MPa							o	
17			82 (54)									
18						HW-MW MW-SW					Is(50)=0.47 MPa Is(50)=0.46 MPa	x o
19											Is(50)=0.48 MPa Is(50)=0.32 MPa	o x
20	-21.09		89 (87)		SILTSTONE FINE GRAINED THINLY LAMINATED SEDIMENTARY ROCK SW : Pale grey to grey, fine grained, thinly laminated, mainly medium strength.	SW					Is(50)=0.42 MPa Is(50)=0.56 MPa	x o
20	-21.84											

REMARKS This borelog should be read in conjunction with the appropriate Defect Description Sheets. Defect angles have been measured with respect to a horizontal plane.

LOGGED BY
A. DISSANAYAKE (DISS)



**Queensland
Government**

Department of
Main Roads

ENGINEERING BOREHOLE

FOR GEOTECHNICAL TERMS AND
SYMBOLS REFER FORM F:GEOT 017/2-2004

BOREHOLE No BH11

SHEET 6 of 6

REFERENCE No H9560

PROJECT GATEWAY UPGRADE PROJECT - GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION PIER 6 - SOUTHERN FACE OF THE PILE CAP COORDINATES 10316.4 E; 167691.5 N

PROJECT No FG5388 SURFACE R.L. -1.84 DATE STARTED 10/3/05 DATUM SETP

JOB No _____ DATUM AHD DATE COMPLETED 11/3/05 DRILLER CAIRNS DRILLING

DEPTH (m)	R.L. (m)	CASING WASH BORING CORE DRILLING	RQD (%)	CORE REC %	SAMPLE	MATERIAL DESCRIPTION	LITHOLOGY	WEATHERING						GRAPHIC LOG	ADDITIONAL DATA AND TEST RESULTS	SAMPLES TESTS		
								USC	EH	VH	H	M	J				VL	EL
25	-26.84					MUDSTONE SW : Dark grey to black, fine grained, thinly laminated, low to mainly medium strength.												
	-26.99		100			Defects : Generally rare. Occasional drilling induced lamination partings <10° (1/m) and irregular fractures. Borehole terminated at 25.15m		SW										
26																		
27																		
28																		
29																		
30																		

BOREHOLE WITH LITHOLOGY MEERA PIER 6 BOREHOLES-GATEWAY BRIDGE - GATEWAY UPGRADE PROJECT.GPJ ENGINEERING BOREHOLE 09_04.GDT 31/8/05

REMARKS This borelog should be read in conjunction with the appropriate Defect Description Sheets. Defect angles have been measured with respect to a horizontal plane.

LOGGED BY
A. DISSANAYAKE (DISS)

Project: **Gateway Upgrade Project - Gateway Bridge**

Borehole No: **BH 11**

Start Depth: 8.10m

Finish Depth: 25.15m

Project No: FG 5388

H No: ????



Project: **Gateway Upgrade Project - Gateway Bridge**

Borehole No: **BH 11**

Start Depth: 8.10m

Finish Depth: 25.15m

Project No: FG 5388

H No: ????



DEFECT DESCRIPTIONS OF ENGINEERING BORELOGS

[CHARACTERISATION OF DEFECTS ARE IN ACCORDANCE WITH
ISRM SUGGESTED METHODS (1981)]

BOREHOLE NO : BH11

SHEET : 1 of 5

REFERENCE NO : H9560

PROJECT : GATEWAY UPGRADE PROJECT – GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION : PIER 6 - SOUTHERN FACE OF THE PILE CAP

PROJECT NO : FG5388 SURFACE R.L. : -1.84 DRILLER : CAIRNS DRILLING PTY LTD

JOB NO : DATUM : AHD DATE DRILLED : 10-11/03/05

DEPTH	DEFECT TYPE	DIP	PLANARITY	ROUGHNESS	APERTURE	WALL ALTERATION	OTHER
8.1-8.3	-	-	-	-	-	-	Core loss
8.3-8.39	BZ	-	-	-	-	Cn	BP
8.39	BP	20°	P	S	O	Cn	Polished
8.50-8.75	WS	-	-	-	-	W	Gravelly clay
8.86-8.87	WS/BZ	-	-	-	-	W	-
9.05-9.33	WS/BZ	-	-	-	-	W	BP
9.38	LP	<10°	P	S	O	Cn	-
9.39-9.44	WS/BZ	<10°	P	S	C	W	-
9.40-9.47	WS/BZ	-	-	-	-	W	-
9.44	LP	<10°	P	S	O	Cn	-
9.49	LP	<10°	P	S	C	Cn	LP
9.52	LP	<10°	P	S	C	Cn	-
9.56	LP	<10°	P	S	C	Cn	-
9.6-10.0	-	-	-	-	-	-	Core loss
10.0-10.06	WS/BZ	-	-	-	-	W	-
10.0-10.12	WS/BZ	-	-	-	-	W	-
10.21-10.24	WS	-	-	-	-	W	BP
10.30-10.32	WS	-	-	-	-	W	-
10.35-10.37	WS	-	-	-	-	W	-
10.40-10.54	WS	-	-	-	-	W	BP
10.61	LP	-	P	S	O	Cn	-
10.61-10.69	WS	-	-	-	-	W	BP

Abbreviations

ROUGHNESS		WALL ALTERATIONS		TYPE		OTHER	
R	Rough	FeSt	Iron Stained	J	Joint	DI	Drilling Induced
S	Smooth	W	Weathered	B	Bedding	CL	Carbonaceous lamination
SL	Slickensided	SM	Secondary Mineralisation	BP	Bedding Parting	Co	Coal seam
				FP	Foliation Parting	In	Incipient
				LP	Lamination Parting	SI	Sand Infill
PLANARITY		APERTURE					
P	Planar	C	Closed	SZ	Sheared Zone	H	Horizontal
St	Stepped	O	Open	CZ	Crushed Zone	V	Vertical
Un	Undulating	F	Filled	WS	Weathered Seam	CI	Clay Infill
Cu	Curved	T	Tight	BZ	Broken Zone	Cn	Clean
Ir	Irregular			HFZ	Highly Fractured Zone	CS	Clay Seam
				Fr	Fracture		

NOTE: This sheet should be read in conjunction with appropriate Engineering Borelog. Defect angles were measured with respect to horizontal plane.

DEFECT DESCRIPTIONS OF ENGINEERING BORELOGS

[CHARACTERISATION OF DEFECTS ARE IN ACCORDANCE WITH
 ISRM SUGGESTED METHODS (1981)]

BOREHOLE NO : BH11

SHEET : 2 of 5

REFERENCE NO : H9560

PROJECT : GATEWAY UPGRADE PROJECT – GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION : PIER 6 – SOUTHERN FACE OF THE PILE CAP

PROJECT NO : FG5388 SURFACE R.L. : -1.84 DRILLER : CAIRNS DRILLING PTY LTD

JOB NO : DATUM : AHD DATE DRILLED : 10-11/3/05

DEPTH	DEFECT TYPE	DIP	PLANARITY	ROUGHNESS	APERTURE	WALL ALTERATION	OTHER
10.75	LP	<10°	P	S	C	Cn	-
10.98	LP	15°	P	S	C	Cn	-
11.0	LP	20°	P	S	O	Cn	-
11.0	LP	15°	P	S	C	Cn	-
11.11	LP	20°	P	S	O	-	CI
11.14	LP	20°	P	S	O	Cn	-
11.21	LP	10°	P	-	O	Cn	-
11.30-11.32	WS	-	-	-	-	W	-
11.35-11.37	WS	-	-	-	-	W	-
11.51-11.54	BZ/WS	-	-	-	-	W	-
11.61	LP	15°	P	-	-	Cn	-
11.79-11.96	BZ	-	-	-	-	Cn	-
11.98	LP	15°	P	S	C	Cn	-
12.0-12.73	-	-	-	-	-	-	Coreloss
12.73-12.92	WS/BZ	-	-	-	-	W	-
12.97-13.01	BZ	-	-	-	-	Cn	-
13.10-13.15	BZ/WS	-	-	-	-	W	-
13.5-13.70	BZ/WS	-	-	-	-	W	-
13.80	BP/LP	-	-	-	-	Cn	-
13.81-13.85	WS/BZ	-	-	-	-	W	-
14.05	LP	-	P	S	O	-	-

Abbreviations

ROUGHNESS		WALL ALTERATIONS		TYPE		OTHER	
R	Rough	FeSt	Iron Stained	J	Joint	DI	Drilling Induced
S	Smooth	W	Weathered	B	Bedding	CL	Carbonaceous lamination
SL	Slickensided	SM	Secondary Mineralisation	BP	Bedding Parting	Co	Coal seam
				FP	Foliation Parting	In	Incipient
				LP	Lamination Parting	SI	Sand Infill
P	Planar	C	Closed	SZ	Sheared Zone	H	Horizontal
St	Stepped	O	Open	CZ	Crushed Zone	V	Vertical
Un	Undulating	F	Filled	WS	Weathered Seam	CI	Clay Infill
Cu	Curved	T	Tight	BZ	Broken Zone	Cn	Clean
Ir	Irregular			HFZ	Highly Fractured Zone	CS	Clay Seam
				Fr	Fracture		

NOTE: This sheet should be read in conjunction with appropriate Engineering Borelog. Defect angles were measured with respect to horizontal plane.

DEFECT DESCRIPTIONS OF ENGINEERING BORELOGS

[CHARACTERISATION OF DEFECTS ARE IN ACCORDANCE WITH
ISRM SUGGESTED METHODS (1981)]

BOREHOLE NO : BH11
SHEET : 3 of 5
REFERENCE NO : H9560

PROJECT : GATEWAY UPGRADE PROJECT – GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION : PIER 6 – SOUTHERN FACE OF THE PILE CAP

PROJECT NO : FG5388 SURFACE R.L : -1.84 DRILLER : CAIRNS DRILLING PTY LTD

JOB NO : DATUM : AHD DATE DRILLED : 10-11/3/05

DEPTH	DEFECT TYPE	DIP	PLANARITY	ROUGHNESS	APERTURE	WALL ALTERATION	OTHER
14.08-14.10	BZ/WS	-	-	-	-	W	-
14.28-14.29	BZ	-	-	-	-	-	Parallel to LP
14.60	LP	-	P	S	T	-	DI
14.74-14.75	CS	-	-	-	-	-	CI
14.82-15.05	BZ	-	-	-	-	-	Parallel to LP
15.18	LP	P	S	-	-	Cn	-
15.28	LP	P	S	-	-	Cn	-
15.31	LP	P	S	-	-	Cn	-
15.34	LP	P	S	-	-	Cn	-
15.5	LP	P	S	-	-	Cn	-
15.6	LP	P	S	-	-	Cn	-
15.68	LP	P	S	-	-	W	-
15.76-15.78	BZ	-	-	-	-	Cn	Parallel to LP
15.91	LP	P	S	O	-	Cn	-
16.27	LP	P	S	O	-	Cn	-
16.3-16.35	WS/BZ	-	-	-	-	W	Parallel to LP
16.41-16.48	WS/BZ	-	-	-	-	W	Parallel to LP
16.54-16.60	WS/BZ	-	-	-	-	W	Parallel to LP
16.65-16.70	BZ	-	-	-	-	Cn	-
16.72-17.40	-	-	-	-	-	-	Coreloss
17.40-17.50	BZ/WS	-	-	R	O	W	-
17.68-17.78	WS	-	-	-	O	W	Parallel to LP

Abbreviations

ROUGHNESS		WALL ALTERATIONS		TYPE		OTHER	
R	Rough	FeSt	Iron Stained	J	Joint	DI	Drilling Induced
S	Smooth	W	Weathered	B	Bedding	CL	Carbonaceous lamination
SL	Slickensided	SM	Secondary Mineralisation	BP	Bedding Parting	Co	Coal seam
				FP	Foliation Parting	In	Incipient
				LP	Lamination Parting	SI	Sand Infill
P	Planar	C	Closed	SZ	Sheared Zone	H	Horizontal
St	Stepped	O	Open	CZ	Crushed Zone	V	Vertical
Un	Undulating	F	Filled	WS	Weathered Seam	CI	Clay Infill
Cu	Curved	T	Tight	BZ	Broken Zone	Cn	Clean
Ir	Irregular			HFZ	Highly Fractured Zone	CS	Clay Seam
				Fr	Fracture		

NOTE: This sheet should be read in conjunction with appropriate Engineering Borelog. Defect angles were measured with respect to horizontal plane.



**DEFECT DESCRIPTIONS
OF ENGINEERING BORELOGS**

[CHARACTERISATION OF DEFECTS ARE IN ACCORDANCE WITH
ISRM SUGGESTED METHODS (1981)]

BOREHOLE NO : BH11

SHEET : 4 of 5

REFERENCE NO : H9560

PROJECT : GATEWAY UPGRADE PROJECT - GATEWAY BRIDGE DUPLICATION FOUNDATION INVESTIGATION

LOCATION : PIER 6 - SOUTHERN FACE OF THE PILE CAP

PROJECT NO : FG5388 SURFACE R.L. : -1.84 DRILLER : CAIRNS DRILLING PTY LTD

JOB NO : DATUM : AHD DATE DRILLED : 10-11/3/05

DEPTH	DEFECT TYPE	DIP	PLANARITY	ROUGHNESS	APERTURE	WALL ALTERATION	OTHER
17.83	LP	<5°	-	-	O	Cn	-
17.89-17.93	WS	-	-	-	O	W	-
18.14-18.17	WS	-	-	-	-	W	-
18.38	LP	<5°	Cu	R	-	Cn	-
18.45-18.54	BZ	-	-	-	C	Cn	CS
18.61	BP	<5°	P	S	C	Cn	LP
18.69-18.85	BZ	10°	P	-	C	Cn	-
19.25	LP	10°	Ir	R	-	W	-
19.29-19.33	BZ	-	-	-	O	Cn	Partly broken
19.61-19.68	WS	-	-	-	O	W	-
19.77-19.81	BZ	-	-	R	O	Cn	LP
19.96	Fr	-	Ir	-	C	Cn	Parallel to LP
20.08	J	35°	Un	R	O	Cn	DI
20.25	J	35°	P/Ir	R	T	Cn	DI
20.35	J	35°	Ir	R	T	Cn	DI
20.38	J	35°	Ir	R	T	Cn	DI
20.50	LP	20°	P	R	T	Cn	DI
20.69	LP	<10°	Cu	R	T	Cn	DI
20.79	LP	<10°	Cu	R	T	Cn	DI
20.91	LP	<10°	Ir	R	T	Cn	DI
21.20	LP	<5°	P	R	T	Cn	DI

Abbreviations

ROUGHNESS		WALL ALTERATIONS		TYPE		OTHER	
R	Rough	FeSt	Iron Stained	J	Joint	DI	Drilling Induced
S	Smooth	W	Weathered	B	Bedding	CL	Carbonaceous lamination
SL	Slickensided	SM	Secondary Mineralisation	BP	Bedding Parting	Co	Coal seam
				FP	Foliation Parting	In	Incipient
				LP	Lamination Parting	SI	Sand Infill
PLANARITY		APERTURE					
P	Planar	C	Closed	SZ	Sheared Zone	H	Horizontal
St	Stepped	O	Open	CZ	Crushed Zone	V	Vertical
Un	Undulating	F	Filled	WS	Weathered Seam	CI	Clay Infill
Cu	Curved	T	Tight	BZ	Broken Zone	Cn	Clean
Ir	Irregular			HFZ	Highly Fractured Zone	CS	Clay Seam
				Fr	Fracture		

NOTE: This sheet should be read in conjunction with appropriate Engineering Borelog. Defect angles were measured with respect to horizontal plane.



**DEFECT DESCRIPTIONS
OF ENGINEERING BORELOGS**

[CHARACTERISATION OF DEFECTS ARE IN ACCORDANCE WITH
ISRM SUGGESTED METHODS (1981)]

BOREHOLE NO : BH11

SHEET : 5 of 5

REFERENCE NO : H9560

PROJECT : GATEWAY UPGRADE PROJECT – GATEWAY BRIDGE DUPLICATION FOUNDATION
INVESTIGATION

LOCATION : PIER 6 – SOUTHERN FACE OF THE PILE CAP

PROJECT NO : FG5388 SURFACE R.L : -1.84 DRILLER : CAIRNS DRILLING PTY LTD

JOB NO : DATUM : AHD DATE DRILLED : 10-11/3/05

DEPTH	DEFECT TYPE	DIP	PLANARITY	ROUGHNESS	APERTURE	WALL ALTERATION	OTHER
21.30-21.60	BZ	-	-	-	-	Cn	Parallel to LP
21.50	J	45-50°	Un	R	O	Cn	-
22.23	Fr	<10°	Ir	R	O	Cn	DI
22.28-22.92	BZ	-	-	-	-	-	CI
22.90-23.18	BZ	-	-	-	C	Cn	-
23.10-23.20	Fr	70°	St	R	C	Cn	-
23.14-23.19	SZ	45°	Ir	-	C	Cn	-
23.30-23.60	Fr	60-90°	Ir	R	T	Cn	DI?
23.65	LP	<10°	P	S	C	Cn	CL
23.71	J	35°	Ir	R	-	Cn	?
23.76	LP	<10°	P	S	C	Cn	-
23.85-23.96	BZ	-	-	-	-	Cn	Parallel to LP
24.51	LP	<10°	P	R	C	Cn	-
24.64	BZ	-	-	-	C	Cn	Parallel to LP

Abbreviations

ROUGHNESS		WALL ALTERATIONS		TYPE		OTHER	
R	Rough	FeSt	Iron Stained	J	Joint	DI	Drilling Induced
S	Smooth	W	Weathered	B	Bedding	CL	Carbonaceous lamination
SL	Slickensided	SM	Secondary Mineralisation	BP	Bedding Parting	Co	Coal seam
				FP	Foliation Parting	In	Incipient
				LP	Lamination Parting	SI	Sand Infill
PLANARITY		APERTURE					
P	Planar	C	Closed	SZ	Sheared Zone	H	Horizontal
St	Stepped	O	Open	CZ	Crushed Zone	V	Vertical
Un	Undulating	F	Filled	WS	Weathered Seam	CI	Clay Infill
Cu	Curved	T	Tight	BZ	Broken Zone	Cn	Clean
Ir	Irregular			HFZ	Highly Fractured Zone	CS	Clay Seam
				Fr	Fracture		

NOTE: This sheet should be read in conjunction with appropriate Engineering Borelog. Defect angles were measured with respect to horizontal plane.